

# CITY OF DE PERE

## Engineering Division

925 S. Sixth Street, De Pere, WI | 920-339-4061 | [www.deperewi.gov/engineering](http://www.deperewi.gov/engineering)



March 27, 2025

ADDENDUM NO. 1  
PROJECT 25-02  
NORTHEAST STREET RECONSTRUCTION AND UTILITY RELAY

TO: Prospective Bidders

FROM: City of De Pere

Notice is hereby given that the contract documents for Project 25-02 are amended as hereinafter set forth. If you are submitting a bid for Project 25-02, you must sign this addendum and include it with your submittal.

This addendum consists of 4 pages.

#### CHANGES TO PROJECT BID DOCUMENTS:

1. Section 00 41 43, Bid Schedule, delete page 3 and insert page 3R. The quantity for Bid Item ST-13 has been changed from 15 VF to 5 VF. The amount will be corrected on the QuestCDN website.
2. Section 00 41 43, Bid Schedule, delete page 6 and insert page 6R. The quantity changes are as follows below. The amounts will be corrected on the QuestCDN website.
  - a. The quantity for Bid Item SD-12 has been changed from 5650 LF to 5465 LF
  - b. The quantity for Bid Item SD-14 has been changed from 40 LF to 225 LF.

#### CHANGES TO GENERAL REQUIREMENTS

1. Section 01 22 04, Measurement & Payment Street & Drainage Construction. Under 1.8 Portland Cement Concrete Curb and Gutter, B., Insert the following:
  - "1. Bid Item SD-12 Remove and Replace 24" Concrete Curb and Gutter (Slip Form) applies to all areas where slip form curb and gutter is installed. Slip form curb shall be used in all areas unless approved by the Engineer.
  2. Bid Item SD-13 Remove and Replace 24" Concrete Curb and Gutter (Hand Excavate and Form at Trees) applies to areas near trees as shown on the plans or where directed by the Engineer.

3. Bid Item SD-14 Remove and Replace 24" Curb and Gutter applies to the integral curb on concrete pavement, and other areas within the project where standard excavation occurs but concrete curb and gutter is installed with forms and hand work. These locations include gaps between Bid Item SD-13.

Sincerely,

DEPARTMENT OF PUBLIC WORKS



Eric P. Rakers, P.E.  
City Engineer



Acknowledged by: \_\_\_\_\_ Date: \_\_\_\_\_

**Project 25-02**  
**Northeast Street Reconstruction and Utility Relay**

**City of De Pere**

ITEM	ITEM DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	AMOUNT BID
<b>STORM SEWER (Continued)</b>					
ST-04	Provide 12" RCP (Class III), PP or PVC Storm Sewer (Granular Backfill)	LF	950	\$	\$
ST-05	Provide 8" PVC Storm Sewer (Granular Backfill)	LF	770	\$	\$
ST-06	Provide 6" PVC Storm Sewer Lateral	LF	1050	\$	\$
ST-07	Provide 4" PVC Storm Sewer Lateral	LF	80	\$	\$
ST-08	Provide 24"x6" Storm Branch or Inserta Tee	EA	6	\$	\$
ST-09	Provide 15"x6" Storm Branch or Inserta Tee	EA	4	\$	\$
ST-10	Provide 12"x6" Storm Branch or Inserta Tee	EA	8	\$	\$
ST-11	Provide 8"x6" Storm Branch or Inserta Tee	EA	10	\$	\$
ST-12	Provide Storm Sewer Lateral Tracer Wire Box	EA	26	\$	\$
ST-13	Provide 60" Diameter Storm Manhole	VF	5	\$	\$
ST-14	Provide 48" Diameter Storm Manhole	VF	70	\$	\$
ST-15	Remove and Replace 60" Storm Manhole	VF	7	\$	\$
ST-16	Remove and Replace Type A Catch Basin	EA	1	\$	\$
ST-17	Provide Type B Catch Basin	EA	10	\$	\$
ST-18	Provide Type B Inlet	EA	7	\$	\$
ST-19	Remove and Replace Type B Inlet	EA	1	\$	\$

**Project 25-02**  
**Northeast Street Reconstruction and Utility Relay**

**City of De Pere**

ITEM	ITEM DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	AMOUNT BID
<b>STREET AND DRAINAGE (Continued)</b>					
SD-10	Provide Large Asphalt Patch	SY	20	\$	\$
SD-11	Provide Small Asphalt Patch	SY	10	\$	\$
SD-12	Remove and Replace 24" Concrete Curb and Gutter (Slip Form)	LF	5465	\$	\$
SD-13	Remove and Replace 24" Concrete Curb and Gutter (Hand Excavate and Form at Trees)	LF	200	\$	\$
SD-14	Remove and Replace 24" Concrete Curb and Gutter	LF	225	\$	\$
SD-15	Remove and Replace 8" Concrete Pavement with Integral Curb	SY	240	\$	\$
SD-16	Remove and Replace 8" Concrete Sidewalk, Ramp, and Driveway	SY	70	\$	\$
SD-17	Remove and Replace 6" Concrete Sidewalk, Ramp, and Driveway	SY	480	\$	\$
SD-18	Remove and Replace 4" Concrete Sidewalk	SY	750	\$	\$
SD-19	Provide #4 Reinforcement Bars for Curb and Sidewalk	LF	2600	\$	\$
SD-20	Drilled Tie Bars (Existing Sidewalk, Driveway, and Curb and Gutter)	EA	280	\$	\$
SD-21	Drilled Dowel Bars	EA	100	\$	\$
SD-22	Drilled Tie Bars (Concrete Pavement)	EA	35	\$	\$
SD-23	Provide Detectable Warning Field (Natural)	EA	25	\$	\$
SD-24	Landscaping – Topsoil, Seed, Fertilizer and Mulch	SY	3100	\$	\$